



# **MARINWOOD PARK PLAYGROUND: PLAY STRUCTURES REPLACEMENT PROJECT**

## **ADDENDUM NO. 1**

**DATE:** May 11, 2023

**TO:** All Prospective Bidders

**RE:** Protective Surfacing Clarification:  
Existing Conditions and Vendor Requirements

The purpose of this Addendum No. 1 is to clarify Protective Surfacing requirements as it pertains to the Request for Proposals (RFP) issued on May 1, 2023 by Marinwood Community Services District for the “Marinwood Park Playground: Play Structures Replacement Project.” This Addendum shall be considered a part of the aforementioned RFP and shall be incorporated therein.

### **PROTECTIVE SURFACING**

Procurement and installation of new protective surfacing (i.e. “fall material”) is not an aspect of this RFP to be included in Vendor proposals.

The protective surfacing (“fall material”) currently installed in both the Marinwood Park Main Playground and Tot Playground consists of Engineered Wood Fiber (EWF) maintained at a depth of 9-12 inches in all play equipment use zones. Under the current protective surfacing conditions, all proposed new playground equipment must have a maximum Fall Height (i.e. the vertical distance between the highest accessible designated play surface of the play equipment and the protective surfacing below it) no greater than 10 feet.

It is the expectation for this project that the existing “fall material” will be preserved, maintained and redistributed upon conclusion of play equipment installation. While it is expected the awarded Vendor shall make all reasonable efforts to do so, it is recognized that in the course of removal of existing play equipment and installation of new play equipment it may not be possible to preserve 100% of the existing fall material and redistribute appropriately at the existing depth. In such instances, additional fall material may be needed for certification purposes. The procurement and installation costs of any needed additional fall material shall be the responsibility of the District.